

Type the following specification in the blocked style. Use current date.

Specification of work to be carried out and materials to be used at 34 Perseverance Road, Couva in the construction of a bridge opposite the driveway for Mr Allan Potter to the satisfaction of:

Ramroop & Company
Architect & Surveyor
Lime Head Road
CARAPICHAIMA

General Conditions

Visit of Site

The contractor should visit the site before starting the project so as to acquaint himself with the nature of the environment.

U/S → Accountability

The Contractor must instruct his workers not to damage any vegetable crops or existing drains when carting away excavated material to the back of the lot. The Contractor will be held accountable for any damages.

SITE CLEARANCE

Cutlass grass, dig out grass roots and remove them from the site.

FOUNDATION

Excavation

Excavate ^{oversite} on both sides of the drain 10 cm deep ^{by 30 cm long} to remove vegetable soil.

Excavate drain 20 cm deep to remove slush.

To receive foundation

Excavate trench on both sides of drain 15 cm wide by 30 cm deep for retaining wall.

Load and cart away material excavated to the back of the lot.

Ramming

Level and ram bottom of excavation to receive concrete.

Steel Work

Tie steel structure and lay on both trenches to receive retaining wall.

Concrete

at the bottom of the drain

Spread 10 cm concrete (3:2:1) 20 mm aggregate to facilitate easy cleaning afterwards on both trenches.

GO ON TO THE NEXT PAGE